

HICKORY, INDIANA / TECHNICAL LIBRARY

Gym Equipment Coordination Guide

An architect and contractor checklist for early athletic equipment coordination.

Early project inputs

- + Room dimensions and reflected ceiling plan
- + Court layouts and activity schedule
- + Structural framing and available attachment zones
- + Power and control locations
- + Equipment storage and changeover routes
- + Owner access and supervision requirements

Overhead coordination matrix

Basketball backstops	Playing position, folded position, attachment height, bracing, controls
Divider curtains	Travel path, roll or fold volume, lighting and sprinkler conflicts
Volleyball	Sleeve locations, cover plates, post storage, referee stand
Controls	Owner access, grouping, labeling, line voltage and low voltage
Service	Lift access, inspection space, safe isolation

Submittal review prompts

- + Do model numbers match the equipment schedule?
- + Do dimensions match the architectural and structural backgrounds?
- + Are loads and attachment concepts identified?
- + Are operating controls and electrical requirements coordinated?
- + Are finishes and graphics approved?
- + Is the installation sequence compatible with the project schedule?